

555 Oak Street East North Bay, Ontario P1B 8L3 555, rue Oak Est North Bay (Ontario) P1B 8L3

Tel: 1-800-363-7512 www.ontarionorthland.ca

November 17, 2025

Addendum No. 01

File Reference Number: RFP 2025 093

Title: Engineering Services for Truck Shop Expansion

RE: Clarifications/Questions

QUESTIONS/CLARIFICATIONS:

Item 1: Does the ONTC have any site servicing records that they can share?

Answer: ONTC doesn't have much for records.

Item 2: Please confirm if a subsurface utility investigation will be required.

Answer: ONTC will provide locates.

Item 3: Will the ONTC be providing a topographic survey or is the proponent required to complete this?

Answer: Please refer to the Topographic Surveys attached at the end of this Addendum at Appendix A.

Item 4: Will the ONTC be providing design and specifications for the track design or is the proponent required to complete this?

Answer: Please refer to ONTC's Track Specifications attached at the end of this Addendum at Appendix B.

Item 5: Would it be possible to obtain the pre-engineered building drawings?

Answer: The existing building drawings are provided in the RFP at Appendix

Item 6: Are we to investigate the entire structure and make as-built drawings of the existing structure? Or are we to tie in the new structure with the existing

Answer: According to our Building Condition Assessment, the existing structure is in good condition. The intent is to tie the new structure into the existing.

Item 7: What is the height of the new addition?

Answer: Match the existing building height that is indicated in the original drawing set, elevation - drawing 4 (Page 4) of the RFP.

Item 8: Is the locomotive addition to be included in this proposal – if says future – there will be snow loading on the existing pre-Eng. Building?

Answer: A conceptual design shall be included for the locomotive addition only. This will be used budgetary purposes. Provide a summary and quote items if additional engineering services are required on the existing building for the snow loading.

Item 9: Are we responsible for Site Plan Approval (SPA) process, specifically providing the photometric design for the outdoor lighting?

Answer: No, ONTC wouldn't be concerned about this since the outdoor building lighting will be at the back of the building and away from the local city roadways and streets.

Item 10: Will the electrical engineer be responsible for coordinating the power upgrade with the local utility supplier, or will this coordination be handled by others?

Answer: The electrical engineer shall coordinate the power upgrade with the local utility supplier, and this shall be added to the Contract Administration Fees.

Item 11: In lieu of a Subject Matter Expert, would ONTC consider the prime consultant preparing a performance specification for the competitive bidding of turnkey spray booth and blast booth? It will offer a superior product, better service, and a more competitive pricing.

Answer: Yes, ONTC will consider this if the consultant can provide a turnkey solution for the spray and blast booths and can clearly indicate what will be included in the performance specification to meet the RFP evaluation criteria and mandatory requirements.

Item 12: Will ONTC agree to extend the submission deadline for this RFP?

Answer: Yes. The revised submission deadline is now **Friday, November 28, 2025 at 2:00:00 p.m.**

Please be advised that <u>Section 1.6.1 - Key Dates</u> of the RFP has been updated. The revised table is provided below for your reference.

1.6.1 Key Dates

Issue Date of RFP	Monday, November 03, 2025
Mandatory Site Visit	Not Applicable
Deadline for Questions	Monday, November 24, 2025
Deadline for Issuing Addenda	Wednesday, November 26, 2025
Submission Deadline	Friday, November 28, 2025 at 2:00:00 local time
Irrevocability Period	Ninety (90) calendar days

The RFP timetable is tentative only and may be changed by ONTC at any time.

Item 13: Please refer to revised Appendix B – RFP Particulars sections as follows:

• Section D – Mandatory Technical Requirements

Mandatory Requirement	Revised Mandatory Requirement
Paint, Blast, and Wash Booth Subject Matter Expert (SME) shall have at least five (5) years of proven experience in designing and supplying Paint and Blast booths. Subject Matter Expert should have experience working with Blast One, Nova Finishing Products, or an equivalent equal	Paint, Blast, and Wash Booth Subject Matter Expert (SME) shall have at least five (5) years of proven experience in designing and supplying Paint and Blast booths. Subject Matter Expert should have experience working with Blast One, Nova Finishing Products, or an equivalent equal. A prime consultant, rather than an SME, will also be considered if they can explain in detail how they can provide a performance specification for a turnkey spray booth and blast booth solution for competitive bidding.

 Section F - Evaluation Criteria - Technical Proposal Contents - Item No. 1.3: Experience and Qualifications:

Description	Revised Description		
shall demonstrate their knowledge and expertise by providing references for three (3) projects of similar size and scope to confirm that Proponents has the experience and	Experience and Qualifications: Proponents shall demonstrate their knowledge and expertise by providing references for three (3) projects of similar size and scope to confirm that Proponents has the experience and resources to complete the project. The project descriptions shall include:		
a) Client name and contact detailsb) Project scope and valuec) Scheduled vs. actual start/end dates	a) Client name and contact detailsb) Project scope and valuec) Scheduled vs. actual start/end dates		

- d) Description of work performed and use of subcontractors
- e) Outcomes (e.g., completed on schedule/budget)

Proponents or their

subconsultants/subcontractor can provide detailed engineering experience of paint and blast booths and/or projects in the railway industry.

ONTC may, in its sole discretion, confirm the Respondent's experience in the projects identified by contacting the named contacts above.

- d) Description of work performed and use of subcontractors
- e) Outcomes (e.g., completed on schedule/budget)

Proponents or their

subconsultants/subcontractor may receive higher scores for demonstrating detailed design and engineering experience related to paint booths and/or relevant projects in the railway industry.

ONTC is not to be provided as a project reference.

ONTC may, in its sole discretion, confirm the Respondent's experience in the projects identified by contacting the named contacts above.

• Section F - Evaluation Criteria - Technical Proposal Contents - Item No. 1.4: Resources


Description Revised Description Resources: Proponents shall demonstrate their ability to fulfil the requirements of the RFP. Resources: Proponents shall demonstrate Include an organizational chart of the proposed their ability to fulfil the requirements of the team, along with their resumes and Paint and RFP. Include an organizational chart of the Blast Booth Subject Matter Expert (SME) as proposed team along with their resumes outlined in the Mandatory Requirements. and Paint and Blast Booth Subject Matter If a proponent decides to provide a Expert (SME) as outlined in the Mandatory performance specification for a turnkey spray booth and blast booth solution for Requirements. competitive bidding, scoring will be determined by the details they provide.

This Addendum hereby forms part of the RFP.

Regards,

Brinda Ranpura
Procurement Contracts Specialist
brinda.ranpura@ontarionorthland.ca

"Appendix A"






ONTC North Bay Rail Yard

Client: Ontario Northland Transit Commission

Project: North Bay Rail Yard Survey

Report Date: October 20, 2023

TULLOCH Project #: 232577





Contents

1. Project Summary	2
1.1 Location:	2
1.2 Client Information:	2
1.3 Coordinate Systems:	2
1.4 Survey Methods:	2
1.5 Project Deliverables:	2
2. Data Processing and QA\QC	3
2.1 ALS Registration Points	3
2.2 ALS Data Acquisition	4
2.3 Data Processing and QA/QC	5
2.4 LiDAR Data Classification	5
2.5 Project Anomalies	5
 Appendix A – ALS Vertical Control report Appendix B – Vertical Control Dz Histogram 	7 11
Figures	
Figure 1 Project Trajectory	4
Tables	
Table 1: ALS Vertical Control Report (Full report is in Appendix	A) 3
Table 2 LiDAR Classification	5



1. PROJECT SUMMARY

1.1 Location:

The Ontario Northland Transportation Commission (ONTC) North Bay rail yard is located in North Bay, Ontario. The site consists of an area that is approximately 0.48 km².

1.2 Client Information:

Company: AECOM

Address: 5090 Explorer Drive Suite 1000 Mississauga, Ontario, L4W 4X6, Canada

Contact Name: Manan Raval Email: manan.raval@aecom.com

1.3 Coordinate Systems:

Acquisition Coordinate System

Reference Frame: NAD83 CSRS 2010 v7

Vertical Datum: CGVD28:78

Projection: UTM 17 Geoid Model: HT 2.0

Units: Meters

1.4 Survey Methods:

Airborne LiDAR Survey

Airborne Survey Aircraft: R 44

Altitude: 300 m AGL Aircraft speed: 70 kts

Laser Scanner: Riegl VQ-480i

Laser Pulse Repetition Rate (PRR): 400 kHz

Airborne Photo Survey

Airborne Survey Aircraft: R 44

Altitude: 1270 m AGL Aircraft speed: 80 kts

Laser Scanner: PhaseOne iXM-100

1.5 Project Deliverables:

- LiDAR data classified per project table in LAS.
- Ground Model Key Points (MKP) in ASCII x,y,z format.
- 0.25m smoothed contours in DWG format.
- 6cm Ortho imagery in Geo Tiff Format



The North Bay Yard LiDAR project involved the acquisition of Airborne LiDAR (ALS) and Orthophoto for approximately 0.5 km² located in North Bay, Ontario. Tasks included collecting project control, performing an airborne LiDAR and Orthophoto survey, generating point cloud and orthophotos. The file deliverables are noted in the Project Deliverable section.

Tulloch employed an airborne LiDAR system to map the area of interest. The survey data was collected onboard a Roberston R-44 on August 4th, 2023. The LiDAR was collected with a Riegl VQ-480i system, and the Orthophoto was collected using a PhaseOne iXM-100 camera.

The VQ-480i Airborne data were processed, checked, and verified for completeness, coverage, and relative integrity. On average, the point density was observed at approximately 40 pts/m² on the hard and flat surfaces in open areas. In the calibration phase, the data were checked in detail for relative alignment (Flightline to Flightline within passes and Flightline pass to Flightline pass) to ensure the data met system and project specifications. The final data were compared to the registration points through a vertical control report, as per Table 1 below.

 Average
 -0.016

 Minimum
 -0.067

 Maximum
 +0.030

 Average Magnitude
 0.018

 RMSe
 0.023

 Std. Deviation
 0.015

Table 1: ALS Vertical Control Report (Full report is in Appendix A)

LiDAR accuracy for the project was met under the project specifications.

2. DATA PROCESSING AND QA\QC

2.1 ALS Registration Points

Registration points were surveyed throughout the project to calibrate and constrain the ALS survey. ALS control points were surveyed using RTK sessions. The RTK sessions were tied to project control by PPP sessions. Registration points have been collected using the following feature codes. The control report in Appendix A contains the following codes: AE: Asphalt Edge, AS: Asphalt String, CB: Catch Basian, CR: Crown of Road, ES: Edge of Shoulder, Gate: Gate line at ground, GS: Gravel String, MH: Maintenance Lid, PS: Paint Striping, SW: Side Walk, Target: Photo Target, and WV: Water Valve.



2.2 ALS Data Acquisition

Data airborne acquisition took place on August 4th, during optimal GPS windows. The project trajectory is displayed as red lines in Figure 1. The Can-Net station in North Bay was used as a base station during the acquisition for both flights. System trajectory was post-processed using kinematic software (TerraPOS).




Figure 1 Project Trajectory



2.3 Data Processing and QA/QC

Data processing began upon airborne acquisition completion, where data were checked for completeness and coverage. Once the trajectory was processed, it was used to register and georeference the point cloud. Next, airborne data were adjusted to the project control using the registration points. The geo-referenced point cloud data was then QA'd using multiple profiles to detect flight lines offset by roll, pitch or heading.

Surface models were created using classified ground points from the LAS. Models were checked for any anomalies in the surface point cloud classification.

2.4 LiDAR Data Classification

The LiDAR data has been classified through automatic routines and manual verification. Points in the LAS data tiles have a class attribute assigned to each point. The used classes are listed in table 2 below.

LiDAR Class	Description
Class 2	Ground
Class 3	Low Vegetation
Class 5	High Vegetation
Class 6	Building
Class 7	Low Point

Table 2 LiDAR Classification

2.5 LiDAR Deliverables

Classified LiDAR data tiles

Calibrated LiDAR strips were processed into 500m x 500m data tiles. An automatic macro was used to generate ground-classified points. The lowest points based on the surrounding points are classified as ground. Points above the ground are then classified as low and high points based on height above the ground classification. Low vegetation are points up to 2m above the ground points. High vegetation are points more than 2m above the ground classified points. An analyst then reviews the auto-classified points to confirm the ground classification. Buildings are then manually classified.

Ground Model Key Points

Ground model Key Points (MKP) are generated from the ground-classified data. MKP represents the minimum number of points required to model the surface. The ground data is first classified based on a 5m grid. If the ground-classified points inside the 5m grid are within +/- 20cm, they are excluded from the MKP data set. This maintains the definition on the surface with the minimum number of points.



0.25m Smoothed Contours

Contours are generated from the ground-classified data. Minor contours are generated at a 0.25m interval. Major contours are generated at 1.25m intervals. Contours have been exported in an AutoCAD dwg format.

2.6 Project Anomalies

No project anomalies were identified while reviewing the LiDAR data or products.



3. APPENDIX A – ALS VERTICAL CONTROL REPORT

00016 37	
20016_AE 619036.059 5128186.259 197.944 197.948 +0.0	04
20021_AE 619030.579 5128183.790 197.774 197.767 -0.0	
20022_CR 619026.863 5128182.698 197.823 197.803 -0.0	
20023_AE 619023.318 5128181.395 197.835 197.798 -0.0	
20030_AE 619030.531 5128163.898 197.847 197.837 -0.0	
20031_CR 619033.886 5128165.096 197.906 197.897 -0.0	
20032_AE 619037.130 5128166.464 197.825 197.815 -0.0	
20037_AE 619041.291 5128168.807 197.867 197.821 -0.0	
20038_AE 619044.500 5128169.955 197.853 197.868 +0.0	
20046_AE 619043.981 5128149.159 197.882 197.871 -0.0	
20047_CR 619040.793 5128147.994 197.958 197.941 -0.0	
20048_AE 619037.508 5128146.820 197.929 197.924 -0.0	
20051_MH 619043.796 5128146.792 197.944 197.911 -0.0	
20052_MH 619010.471 5128208.552 197.683 197.688 +0.0	
20053_MH 619008.804 5128213.277 197.838 197.830 -0.0	
20054_CB 618965.836 5128197.116 197.425 197.413 -0.0	
20055_CB 618969.642 5128185.488 197.418 197.378 -0.0	
20056_PS STOP 618950.036 5128183.348 197.656 197.659 +0.0	
20057_PS STOP 618949.487 5128183.229 197.676 197.671 -0.0	
20058_PS STOP 618946.113 5128193.360 197.553 197.554 +0.0	
20059_PS STOP 618947.083 5128193.026 197.548 197.547 -0.0	
20064_CB 619038.617 5128222.104 197.626 197.582 -0.0	
20065_CB 619075.719 5128226.201 197.970 197.940 -0.0	
20067_AE 618711.981 5128095.752 197.245 197.229 -0.0	
20068_CR 618714.691 5128086.756 197.394 197.391 -0.0 20069_AE 618715.948 5128083.355 197.322 197.308 -0.0	
20069_AE 618715.948 5128083.355 197.322 197.308 -0.0 20072_AE 618717.516 5128078.261 197.415 197.418 +0.0	
20072_AE 618717.516 5128078.281 197.415 197.416 +0.0	
20076_AE 618731.080 5128093.197 197.303 197.284 -0.0	
20077_CR 018731.080 5128093.197 197.409 197.404 -0.0 20078_AE 618728.402 5128100.870 197.254 197.251 -0.0	
20079_SW 618728.448 5128100.918 197.257 197.251 -0.0	
20080_SW 618727.872 5128102.272 197.284 197.281 -0.0	
20085_SW 618745.334 5128109.304 197.306 197.336 +0.0	
20086_SW 618745.860 5128107.955 197.283 197.283 +0.0	
20087_AE 618745.885 5128107.922 197.285 197.284 -0.0	
20088_CR 618748.644 5128099.995 197.391 197.392 +0.0	
20089_AE 618749.974 5128096.803 197.245 197.270 +0.0	
20093_MH 618731.943 5128082.843 197.280 197.256 -0.0	
20094_MH 618722.720 5128089.154 197.333 197.321 -0.0	
20121_PS STOP 618895.513 5128173.942 197.574 197.565 -0.0	
20123_PS STOP 618895.665 5128173.332 197.590 197.581 -0.0	
20124_PS CW 618942.270 5128193.960 197.597 197.600 +0.0	
20126_PS CW 618921.528 5128186.261 197.698 197.682 -0.0	
20127_PS CW 618921.660 5128186.181 197.694 197.686 -0.0	8 0
20095_AS 619935.486 5127573.511 198.666 198.656 -0.0	10
20096_AS 619931.547 5127571.931 198.482 198.474 -0.0	8 0



20097_AE	619929.625	5127571.536	198.451	198.456	+0.005
20097_AE 20098_CR	619926.893	5127570.602	198.481	198.466	-0.015
20098_CR 20099 AE	619922.178	5127569.138	198.400	198.396	-0.013
-					
20108_AE	619929.048	5127551.775	198.307	198.319	+0.012
20109_CR	619932.680	5127553.134	198.339	198.333	-0.006
20110_AE	619936.292	5127554.471	198.341	198.318	-0.023
20111_AS	619938.499	5127555.335	198.366	198.367	+0.001
20112_AS	619942.731	5127557.038	198.640	198.616	-0.024
20113_AS	619948.984	5127540.525	198.046	198.021	-0.025
20114_AS	619945.065	5127538.986	198.258	198.248	-0.010
20115_AE	619942.791	5127538.186	198.243	198.216	-0.027
20116_CR	619939.007	5127536.943	198.290	198.277	-0.013
20117_AE	619935.341	5127535.574	198.252	198.241	-0.011
	619933.021	5127534.706	198.413	198.400	-0.013
20119_AS	619929.543	5127533.310	198.641	198.626	-0.015
20120_MH	619914.468	5127598.022	198.656	198.623	-0.033
20132_MH	619935.631	5127545.646	198.386	198.349	-0.037
20137_AE	620247.180	5127275.457	197.755	197.708	-0.047
20137_AE 20138_CR	620247.180	5127277.933	197.755	197.708	-0.047
	620251.536				-0.033
20139_AE		5127280.153	197.723	197.700	
20144_AS	620271.136	5127273.138	197.828	197.811	-0.017
20145_AS	620268.485	5127270.248	197.714	197.699	-0.015
20146_AE	620266.722	5127268.255	197.630	197.613	-0.017
20147_CR	620264.830	5127265.964	197.703	197.705	+0.002
20148_AE	620262.764	5127263.305	197.687	197.674	-0.013
20152_AS	620273.212	5127246.656	197.744	197.741	-0.003
20153_AS	620275.873	5127249.727	197.651	197.652	+0.001
20154_AE	620277.542	5127251.706	197.697	197.692	-0.005
20155_CR	620279.614	5127254.174	197.762	197.747	-0.015
20156_AE	620281.599	5127256.506	197.647	197.646	-0.001
20163_MH	620284.038	5127250.556	197.749	197.733	-0.016
20169_AE	619552.995	5127821.470	197.839	197.818	-0.021
20170_CR	619555.097	5127824.439	197.894	197.882	-0.012
20171_AE	619557.513	5127827.319	197.829	197.831	+0.002
20185_AE	619572.312	5127815.681	197.828	197.824	-0.004
 20186_CR	619569.974	5127812.606	197.906	197.904	-0.002
20187_AE	619567.825	5127809.749	197.830	197.832	+0.002
20188_AS	619566.331	5127807.915	197.976	197.981	+0.005
20189_AS	619566.194	5127807.688	198.042	198.019	-0.023
20190_AS	619566.036	5127807.497	198.011	198.015	+0.004
20190_AS 20191_AS	619564.909	5127806.088	198.169	198.144	-0.025
20191_AS 20192_AS	619563.790	5127804.724	198.246	198.236	-0.010
	619582.913	5127797.956			+0.002
20199_AE 20200_CR			197.821	197.823	-0.002
_	619585.177	5127800.689	197.908	197.904	
20201_AE	619587.512	5127803.847	197.846	197.856	+0.010
20202_AS	619589.224	5127806.003	198.041	198.035	-0.006
20203_AS	619591.309	5127808.516	198.274	198.259	-0.015
20204_MH	619594.025	5127793.599	197.934	197.913	-0.021
20205_MH	619594.941	5127789.607	197.855	197.852	-0.003
20211_AE	619215.767	5128657.025	203.684	203.664	-0.020
20212_CR	619214.079	5128659.736	203.801	203.774	-0.027
20213_AE	619212.347	5128662.443	203.738	203.732	-0.006
20220_AE	619195.944	5128652.376	204.009	203.993	-0.016



20221_CR	619197.752	5128649.293	204.126	204.079	-0.047
20222_AE	619199.334	5128646.583	204.048	204.016	-0.032
20230_AE	619184.160	5128636.018	204.324	204.293	-0.031
20231_CR	619181.200	5128639.834	204.347	204.327	-0.020
20232_AE	619179.444	5128642.458	204.283	204.260	-0.023
20232_AB 20237_WV	619182.560	5128638.195	201.203	201.200	-0.036
20238_MH	619182.189	5128641.420	204.319	204.304	-0.015
20239_MH	619170.000	5128633.719	204.382	204.347	-0.035
20240_MH	619168.397	5128634.769	204.395	204.334	-0.061
20241_WV	619166.880	5128644.052	204.617	204.588	-0.029
20246_MH	619143.623	5128676.079	203.387	203.349	-0.038
20247_WV	619147.542	5128677.372	203.352	203.336	-0.016
20248_MH	619134.292	5128688.291	204.321	204.313	-0.008
20249_MH	619082.765	5128769.558	207.997	207.950	-0.047
20251_PS	619031.329	5128736.990	204.612	204.584	-0.028
20252_PS	619031.281	5128737.085	204.611	204.584	-0.027
20253_PS	619008.895	5128722.619	203.952	203.929	-0.023
20254_PS	619008.958	5128722.533	203.948	203.932	-0.016
20251_15 20255_WV	619010.589	5128718.557	203.817	203.793	-0.024
	619001.322	5128714.949	203.743	203.793	-0.024
20256_MH					
20257_WV	619006.156	5128709.341	203.502	203.490	-0.012
20259_MH	618993.088	5128722.700	203.933	203.914	-0.019
20260_MH	619018.955	5128686.109	202.849	202.814	-0.035
20262_CB	619036.064	5128651.996	201.965	201.936	-0.029
20263_CB	619043.330	5128642.676	202.110	202.067	-0.043
20264_MH	619043.202	5128648.009	202.275	202.248	-0.027
20265_WV	619035.108	5128643.821	202.213	202.182	-0.031
20266_WV	619033.091	5128642.921	202.172	202.158	-0.014
20270_AE	618984.117	5128607.806	202.273	202.250	-0.023
	618982.395	5128610.928	202.307	202.287	-0.020
	618980.620	5128613.796	202.252	202.252	+0.000
20273_ES	618980.398	5128614.223	202.267	202.266	-0.001
20274_GS	618979.780	5128615.436	202.263	202.276	+0.013
20271_GS 20275_GS	618978.818	5128617.578	202.290	202.274	-0.016
20275_GS 20276_GS	618993.921	5128627.933	202.258	202.274	-0.001
				202.257	
20277_GS	618996.184	5128625.189	202.271	202.260	-0.011
20279_AE	618997.197	5128623.556	202.175		-0.006
20280_CR	618998.799	5128621.180	202.256	202.229	-0.027
20281_AE	619000.879	5128617.963	202.242	202.222	-0.020
20282_AS	619002.003	5128616.138	202.247	202.227	-0.020
20283_AS	619003.436	5128614.319	202.271	202.258	-0.013
20290_AE	619016.310	5128627.846	202.204	202.169	-0.035
20291_CR	619014.703	5128630.610	202.219	202.194	-0.025
20292_AE	619013.624	5128633.785	202.179	202.160	-0.019
20294_GS	619012.650	5128636.201	202.256	202.249	-0.007
20295_GS	619011.059	5128638.727	202.344	202.317	-0.027
	619072.702	5128593.716	201.769	201.737	-0.032
20297_CB	619086.428	5128590.667	201.634	201.591	-0.043
20298_CB	619095.169	5128590.992	201.507	201.460	-0.047
20290_CB	619095.925	5128591.423	201.507	201.100	-0.054
20300_CB	619099.752	5128585.194	201.517	201.403	-0.034
20300_CB 20302_WV	619099.732	5128584.400	201.514	201.483	-0.031
_					
20303_CB	619096.799	5128574.053	201.560	201.528	-0.032



20304_WV	619088.119	5128579.376	201.763	201.751	-0.012
20305_MH	619085.544	5128580.662	201.839	201.813	-0.026
20306_MH	619082.429	5128580.043	201.932	201.920	-0.012
20308_MH	619099.322	5128553.389	201.441	201.417	-0.024
20309_MH	619126.426	5128606.208	201.912	201.901	-0.011
20310_MH	619225.525	5128562.472	202.792	202.755	-0.037
20311_GRATE	619232.334	5128552.902	202.563	202.542	-0.021
20312_GRATE	619231.949	5128552.137	202.593	202.578	-0.015
20313_GRATE	619232.727	5128551.745	202.550	202.550	+0.000
20314_GRATE	619233.093	5128552.510	202.524	202.502	-0.022
20323_AE	620011.579	5128178.609	199.554	199.557	+0.003
20324_CR	620009.800	5128176.184	199.631	199.588	-0.043
20325_AE	620008.013	5128173.823	199.572	199.542	-0.030
20334_AE	620021.869	5128163.359	199.524	199.493	-0.031
20335_CR	620023.606	5128165.857	199.565	199.525	-0.040
20336_AE	620025.119	5128167.976	199.555	199.511	-0.044
20345_AE	620039.595	5128157.201	199.555	199.536	-0.019
20346_CR	620037.734	5128155.146	199.631	199.601	-0.030
20347_AE	620035.802	5128152.816	199.548	199.510	-0.038
20361_AE	619414.476	5128455.230	203.441	203.426	-0.015
20362_CR	619412.209	5128451.900	203.551	203.517	-0.034
20363_AE	619410.477	5128449.030	203.463	203.443	-0.020
20375_AE	619392.201	5128460.776	203.442	203.446	+0.004
20376_CR	619393.760	5128463.659	203.551	203.523	-0.028
20377_AE	619395.504	5128466.453	203.496	203.466	-0.030
20390_AE	619378.619	5128477.984	203.422	203.400	-0.022
20391_CR	619376.397	5128474.877	203.493	203.452	-0.041
20392_AE	619374.070	5128471.612	203.355	203.345	-0.010
25818_TARGET PT	620752.694	5127063.721	197.413	197.415	+0.002



4. APPENDIX B - VERTICAL CONTROL DZ HISTOGRAM




Figure 2 Vertical Control Dz Histogram (LiDAR values minus control)

SKETCH SHOWING TOPOGRAPHIC INFORMATION FOR THE ONTO NORTH BAY SHOP COMPLEX AND UNDERGROUND DRAINAGE TULLOCH GEOMATICS INC. 2023 THE INTENDED PLOT SIZE OF THIS PLAN IS 2159mm IN WIDTH BY 2159mm IN HEIGHT WHEN PLOTTED AT A SCALE OF 1:1000. THE REPRODUCTION, ALTERATION, OR USE OF THIS SKETCH IN WHOLE OR IN PART WITHOUT THE EXPRESS PERMISSION OF TULLOCH GEOMATICS INC. O.L.S. IS STRICTLY PROHIBITED. TOPOGRAPHIC INFORMATION COLLECTED BETWEEN JULY 24 AND NOVEMBER 16, DISTANCES AND ELEVATIONS SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048. COORDINATE SYSTEM: UTM ZONE 17, NAD83 (CSRS) (2010.0) ELEVATION NOTE: ELEVATIONS SHOWN HEREON ARE GEODETIC, ARE REFERRED TO THE CANADIAN GEODETIC VERTICAL DATUM OF 1928 (CGVD28) AND ARE DERIVED FROM REAL TIME NETWORK (RTN) OBSERVATIONS CONTOURS SHOWN ON THIS PLAN ARE DERIVED FROM AIRBORNE LIDAR FLOWN ON AUGUST 4th, 2023. CONTOUR INTERVAL = 0.25m DRAINAGE INVERT NOTE: PLAN TO BE ACCOMPANIED BY PROJECT INVERT CALCULATION SHEET.
PLEASE SEE FILE 232577 ONTC INVERT COMPUTATION SHEET FOR INVERT GEOGRAPHIC LOCATION NOTE: PART OF THE GEOGRAPHIC TOWNSHIP OF WIDDIFIELD AND PART OF THE GEOGRAPHIC TOWNSHIP OF WEST FERRIS IN THE CITY OF NORTH BAY RW DENOTES RETAINING WALL
BLO DENOTES BUILDING
TF DENOTES TRAFFIC LIGHT
CLF DENOTES CHAINLINK FENCE PWF DENOTES POST AND WIRE FENCE BF DENOTES BOARD FENCE HP DENOTES HYDRO POLE

MW DENOTES MONITORING WELL

AN DENOTES POLE ANCHOR

HP DENOTES HYDRO POLE

BP DENOTES BELL POLE

LS DENOTES LIGHT STANDARD

RW DENOTES RETAINING WALL

CSP DENOTES CORRUGATED STEEL PIPE

CP DENOTES CONCRETE PIPE

PP DENOTES PLASTIC PIPE

HDPE DENOTES REINFORCED OPEN CONCRETE CULVERT

BOL DENOTES BOLLARD

SI DENOTES BOLLARD

SI DENOTES SIGN

RKO DENOTES STOCK PILE

FH DENOTES FIRE HYDRANT

WV DENOTES WATER VALVE

RWD DENOTES RAILWAY DERAILER

RSS DENOTES RAILWAY SIGN/SIGNAL

TP DENOTES TELEGRAPH POLE

SBGR DENOTES STEEL BEAM GUARD RAIL HP DENOTES HYDRO POLE SBGR DENOTES STEEL BEAM GUARD RAIL DI DENOTES DITCH INLET MH DENOTES MAINTENANCE HOLE CB DENOTES CATCH BASIN DENOTES TREE DENOTES RAILWAY TOP OF RAIL

DENOTES TREE LINE

X

DENOTES FENCE LINE <u>CAUTION</u>:
This is not a plan of survey and shall not be used except for the purpose indicated in the title block. THE PROPERTY BOUNDARIES ON THIS SKETCH HAVE BEEN COMPILED FROM FIELD SURVEY EFFORTS AND LAND REGISTRY PLANS AND HAVE NOT BEEN CONFIRMED. THIS SKETCH REPRESENTS THE BEST INFORMATION AVAILABLE AT THE TIME OF PREPARATION. THIS SKETCH WAS PREPARED FOR DISCUSSION PURPOSE ONLY AND ASSUMES NO RESPONSIBILITY FOR THE LOCATION OF ANY UNDERGROUND CONDUITS, PIPES OR OTHER FACILITIES WHETHER SHOWN OR OMITTED FROM THIS SKETCH. ALL UNDERGROUND FACILITIES SHOULD BE LOCATED BY THE RESPECTIVE AUTHORITIES PRIOR TO CONSTRUCTION.

APPENDIX A Building Condition Assessment Report



A Substructure A10 Foundations


Element Description	
Name	A101001 - Standard Foundations
Installation Year	1985
Condition	1 - Excellent
Expected Useful Life	75 Years
Remaining Useful Life	38 Years
Renewal Year	2060
Quantity / Unit of Measure	185 / LM Footprint
Unit Cost	\$984.00
Difficulty / Regional / Soft Cost Factors	1.00 / 1.30000 / 1.30000
Replacement Cost	\$307,647.60

Description

The single-storey structure without a basement is constructed on concrete strip-footings that bear on engineered fill.

Condition Narrative

No significant deficiencies were observed or reported on the superstructure to suggest differential settlement of the building foundations. Since this element is mostly below grade and is concealed, no photographs are available to confirm the construction and condition.



North Bay New Maintenance of Way Shop - A101001



North Bay New Maintenance of Way Shop - A101001



North Bay New Maintenance of Way Shop - A101001

Element Description	
Name	A103001 - Slab on Grade
Installation Year	1985
Condition	1 - Excellent
Expected Useful Life	75 Years
Remaining Useful Life	38 Years
Renewal Year	2060
Quantity / Unit of Measure	992 / SM Footprint
Unit Cost	\$71.33
Difficulty / Regional / Soft Cost Factors	1.00 / 1.30000 / 1.30000
Replacement Cost	\$119,583.32

Description

The slab-on-grade, which is likely non-structural, is poured concrete continuously supported likely on a moisture barrier on a free draining gravel layer on engineered fill.

Condition Narrative

No significant deficiencies were observed or reported. At the observed isolated cracks, no significant elevation difference to suggest differential settlement of the concrete slab-on-grade was noted. Recommend that the cracks be monitored and should significantly change be noted a licensed engineer be retained to evaluate the performance of the concrete slab-on-grade.



North Bay New Maintenance of Way Shop - A103001



North Bay New Maintenance of Way Shop - A103001

B ShellB10 Superstructure

Element Description	
Name	B103001 - Structure
Installation Year	1985
Condition	2 - Good
Expected Useful Life	75 Years
Remaining Useful Life	38 Years
Renewal Year	2060
Quantity / Unit of Measure	992 / SM Building
Unit Cost	\$280.00
Difficulty / Regional / Soft Cost Factors	1.00 / 1.30000 / 1.30000
Replacement Cost	\$469,414.40

Description

The building is a pre-engineered steel-framed structure, where tapered columns connected to roof beams support the roof metal deck on purlins.

Condition Narrative

No significant deterioration was noted to suggest movement or twisting of the building structure.



North Bay New Maintenance of Way Shop - B103001



North Bay New Maintenance of Way Shop - B103001

B20 Exterior Enclosure

Element Description				
Name	B201021 - Masonry			
Installation Year	1985			
Condition	1 - Excellent			
Expected Useful Life	75 Years			
Remaining Useful Life	38 Years			
Renewal Year	2060			
Quantity / Unit of Measure	360 / SM			
Unit Cost	\$600.00			
Difficulty / Regional / Soft Cost Factors	1.00 / 1.30000 / 1.30000			
Replacement Cost	\$365,040.00			

Description

The exterior wall system in the office area and grade level of the garage bay are concrete masonry walls, where the face brick is tied to the substrate by brick headers.

Condition Narrative

No significant deficiencies were observed or reported. However, a crack was observed in the southeast entrances. Repair is recommended to keep the system functional.



North Bay New Maintenance of Way Shop - B201021



North Bay New Maintenance of Way Shop - B201021



North Bay New Maintenance of Way Shop - B201021



North Bay New Maintenance of Way Shop - B201021

Recommendations

Recommendations #1 - Masonry			
Туре	Major Repair		
Year	2022		
Cost	\$73,000.00		
Priority	Priority D: Building Functionality		

A crack was observed in the southeast entrances. Repair is recommended to keep the system functional.

"Appendix B"

Prepared Rock Ballast - Specifications

1. Scope

This specification covers the requirements for grading and other significant physical properties of mineral aggregates for prepared ballast.

2. General Requirements

Prepared ballast shall be crushed stone comprised of angular, hard, strong, and durable particles free from injurious amounts of deleterious substances and conforming to the requirements of these specifications.

The Suppliers/Contractor shall, at their own expense, furnish all and every kind of labour, tools, machinery and other plant, services and material whatsoever necessary for the preparation and delivery to the Ontario Northland Transportation Commission (ONTC) of:

- 9,000 tonnes on the Ramore Subdivision at Jardine.
- 20,000 tonnes on the Temagami subdivision at Rabbit Creek Pit.
- 46,000 tonnes on the Devonshire Subdivision between Porquis and Cochrane.

The stone ballast shall be prepared in every respect to the satisfaction of the Rail Infrastructure Department in the manner and upon the terms herein specified and according to specifications below and shall deliver to ONTC in stockpile locations as specified in the RFP Documents and at such time as required by the Rail Infrastructure Department to suit the aforesaid proposals which will form part of the contract.

Please note that crushed rock for the various locations is required as follows:

- The total order must be completed and delivered by June 14, 2024.

Ability to deliver as per the above schedule is of critical importance in the evaluation of the Proposals. In their responses, Respondents must stipulate in writing that they have the material, equipment, and manpower to deliver as required above.

3. Quality Requirements

a) Deleterious substances shall not be present in prepared ballast in excess of the following amounts:

Soft and pliable pieces 5%Material finer than 200 sieve 1%

- b) The percentage of wear of prepared ballast as tested in the Los Angeles machine shall not be greater than 40% except otherwise specified by the Director, Rail Infrastructure.
- c) The soundness of prepared ballast shall be such that when tested in the sodium sulphate or magnesium sulphate soundness tests, the weighted average loss shall not exceed 10% after 5 cycles.

4. Gradation Requirements

- a) The grading of prepared ballast shall be determined by test with laboratory sieves having square openings and conforming to current ASTM specification designated E-11.
- b) Crushed stone prepared ballast shall conform to the following requirements for grading:

		Normal Size Square Opening	Amounts Finer than Each Sieve (Square Opening Laboratory Sieves) % by Weight						
Sieve Size			2"	1 ½"	1"	3/4"	1/2"	3/8"	No.4
% passing	by	$1\frac{1}{2}" - \frac{3}{4}"$	100	90-	20-	0-15		0-5	
Weight				100	55				

5. Washing Ballast

The Supplier/Contractor shall use adequate washing procedures of the crushed stone or suitable dust-control methods to ensure that dust from crushing operation is not carried in the direction of the scales or the stockpile of the prepared stone from where it is loaded in railway hopper cars. If washing and dust control is not included in the unit price (tonne), it must be identified and shown as a separate unit cost on Proposal Form 1 A.

All Rock ballast crushed for Ontario Northland must be washed with high-pressure water nozzles in conjunction with a screening plant. Washing of any ballast will be in the final stage of the crushing operation prior to ballast being dumped into a hopper or waiting trucks.

The washed ballast must meet the acceptance of the Director Rail Infrastructure or his representative. Any ballast which fails to comply with this requirement will be rejected.

6. Handling

Prepared ballast shall be handled at the producing plant in such a manner that is kept clean and free from segregation. It shall be loaded only into trucks which are in good order, tight enough to prevent leakage and waste of material, and which are clean and free from rubbish or any substance which would foul or damage ballast.

7. Scaling and Inspection

The Successful Respondent(s) will be responsible for weighing and inspecting the crushed rock ballast to ensure total compliance with quantity ordered and with all specifications. Successful contractors will be required to provide gradation charts and, from time to time, samples of the crushed rock ballast. ONTC reserves the right of random inspections at the crushing site(s) and to shut down the crushing operation at any time if the crushed rock is not found to meet any and all specifications.

8. Testing

Samples of the finished product for gradation and other required tests shall be taken from each 500 tonnes of prepared ballast, unless otherwise ordered by the Rail Infrastructure Department. The samples shall be representative and shall weigh not less than 50 pounds. The gradation of the samples is plotted on Ontario Northland Drawing No. A-4222 (A).

9. Methods of Test

- a) Samples shall be secured in accordance with the current ASTM Method of Test, designation D75.
- b) Sieve analysis shall be made in accordance with the current ASTM Method of Test, designation C136.
- c) Material finer than the No.200 sieve shall be determined in accordance with the current ASTM Method of Test, designation C117-61T.
- d) The percentage of soft particles shall be determined in accordance with the current ASTM Method of Test, designation C235-57T.
- e) The resistance to abrasion shall be determined in accordance with the current ASTM Method of Test, designation C131-55, using the standard grading most nearly representative of the size of ballast specified.
- f) Soundness tests shall be made in accordance with the current ASTM Method of Test, designation C88-61T.
- g) The weight per cubic foot shall be determined in accordance with the current ASTM Method of Test, designation C29-60.

10. Measurement and Payment

All ballast will be paid for by the tonne, and the Supplier/Contractor shall, at his own expense, provide, install, maintain, and remove scales of sufficient capacity for the measurement of such material. Such scales shall meet the approval of the Rail Infrastructure Department and shall be located at the site where material is produced as directed by a representative of the Rail Infrastructure Department. The Supplier/Contractor shall employ adequate washing of the crushed stone or dust control methods to ensure that the dust from the crushing operation is not carried in the direction of the scales or the stockpile of the prepared stone.

The approach roadway shall be constructed on a flat grade, level with the scale platform for at least one truck length on either side of the platform.

Before commencing to crush, the scales must measure within service limits of error according to Weights and Measures Acts and Regulations. The certification issue by the testing authority of the Government of Canada shall be on view at the scale at all times. Two copies of weight tickets shall be submitted to the Rail Infrastructure Department for every load delivered in this contract with tickets to be provided by the Supplier/Contractor in form required.

An inspector and/or Scaleman may be provided at ONTC's discretion when crushing is in progress.

All trucks used or delivery or finished product from crushing plant to stockpile shall be numbered with tare weight of each truck to be checked daily and shown on weight ticket with truck number. These tickets must be submitted to the Rail Infrastructure Department along with a daily summary of crushing production and stockpiled amounts.

Unit price per tonne of material shall be quoted as follows:

Prepared Stone: To be stockpiled adjacent to the railway at sidings or spurs adjacent to main line track on the Railway System as may be proposed by

the Respondent(s) and acceptable to the ONTC.

11. Sources of Raw Material & Storage Sites

Crushed Stone Ballast

The materials for railway ballast can be waste mine rock or other suitable quarry rock, some of which has been primary crushed and should conform with present environmental regulations regarding the mineral content and its suitability for railway ballast. The Supplier/Contractor of the rock will provide ONTC with a certificate of compliance respecting any and all governing environmental regulations by the Ministry of the Environment of Ontario or any other governing agency. The Supplier/Contractor is to accept full responsibility for size, condition, and location of the raw material relative to the designated location of the proposed stone pile of such material.

Also, once the contract has been completed the Supplier/Contractor shall ensure that the angle of repose of the stockpile is acceptable to the Ministry of Labour standards.

All material produced under this contract shall be delivered to storage site and stockpiled as directed above by ONTC.


Construction and maintenance of the access road and storage area during the term of the contract shall be the responsibility of the Supplier/Contractor.

All the fine material produced under this contract shall remain the property of ONTC and if necessary, shall be stockpiled at a mutually acceptable location away from the crushed rock stockpiled. **If Respondents are interested in retaining the fines, they must**

indicate in their Proposal and state whether the unit price for the crushed rock is net of the retention of the fines or identify unit credit for the fines.

RAIL		DIMEN:	SIONS		PART NUMBERS
SECTION	"A"	"B"max	"B"min	"C"	IMPROVED FAIR
132-6 RE	6.062	0.692	0.652	4.594	600-026XX-01
130 REHF	6.062	0.723	0.683	4.594	600-038XX-01
130 PS	5.562	0.819	0.779	4.094	600-035XX-01
127 DUD	6.312	0.630	0.590	4.844	600-046XX-01
115 RE	5.562	0.692	0.652	4.094	600-070XX-01
105 DUD	5.562	0.546	0.506	4.050	600-094XX-01
100 RA	5.562	0.630	0.590	4.094	600-124XX-01
100 CPRE	5.437	0.645	0.605	3.969	600-130XX-01
100 RE	5.437	0.645	0.605	3.969	600-130XX-01
90 RA	5.187	0.614	0.574	3.719	600-160XX-01

	RAIL		DIMEN:	SIONS		PART NUMBERS
SE	ECTION	"A"	"B"max	"B"min	"C"	IMPROVED FAIR
85	STD	5.062	0.630	0.590	3.594	600-178XX-01
85	ASCE	5.250	0.552	0.512	3.782	600-168XX-01
85	RA	4.937	0.677	0.637	3.469	600-196XX-01
80	ASCE	5.062	0.526	0.486	3.594	600-202XX-01
80	CNOR	5.062	0.558	0.518	3.594	600-206XX-01
80	RA	4.688	0.677	0.637	3.219	600-216XX-01
80	ABS	4.688	0.587	0.547	3.219	600-753XX-01
75	ASCE	4.876	0.549	0.509	3.407	600-228XX-01
75	OBS	4.875	0.562	0.522	3.147	600-766XX-01
65	OBS	4.500	0.532	0.492	2.833	600-765XX-01



NOTES:

- 1. ALL DIMENSIONS IN INCHES.
- 2. DIMENSIONS "B" AND "C" ARE VERIFIED BY THE USE OF THE RAIL ANCHOR GAUGE.
- 3. RAIL ANCHORS TO BE STAMPED WITH THE RAIL SECTION AND YEAR OF MANUFACTURE.
- 4. PART NUMBERS SHOWN ARE FOR BASE UNIT "XX" IS FOR PACKAGING. CALL FOR OPTIONS

SPECIFICATIONS:

MATERIAL: A.I.S.I. C-1060 STEEL HARDNESS RANGE: 311-401 BRINELL

HOLDING POWER AS PER AREMA SPECIFICATIONS

5	FEB. 07, 2017	TABLE AND SPECS CHANGED	SAS
4	MAR 24, 2016	ADDED 65 OBS UPDATED 75 OBS	RGA
3	JUN 16, 2015	ADDED RAIL SECTIONS	RGA
2	DEC. 4, 2014	REVISED PART NUMBERS	RGA
1	DEC. 3, 2014	ISSUED	RGA
ISSUE	DATE	REVISION	BY


LBFoster

Rail Technologies

UNLESS OTHERWISE SPECIFIED TOLERANCES ARE:			NAME				R
DECIMALS ANGLES			IM	PR(DVED	FAIR) ^W
.xx± —	±-			\ 	Λ Λ Γ		
.xxx± —	FR ±-	ACTIONS		→ L	ANCI	$\neg \cup \Gamma \supset$	
DR.	CK.	AP.	DATE	2014	DWG. NO		ISSUE
RGA	GB		DEC. 4	, 2014	107_	0003	L
DO NOT SCALE DRAWING		SCALE NONE	size B	10/	0003)	

90-lb, ARA-A





Rail Type: 90 RA
Section Number: 9020
Nominal Weight: 90 lbs/yd

Standard Length: 39'

Standard Drilling: 2-11/16" X 5-1/2" with 1-1/8" dia. holes

Joint & Angle Bar Lgth: 24"

Angle Bar Weight: 60 lbs/pr with hardware: 67 lbs/pr Joint Bar Weight: 46 lbs/pr with hardware: 53 lbs/pr

Track Bolt: 7/8" X 5"

Area in²: 8.82


Section Modulus in³:

Head: 12.6 Base: 15.2 Moment of Inertia in⁴: 38.7

BOLT SIZE MAY VARY DEPENDING ON BAR MANUFACTURE & TYPE OF WASHER USED.

115-lb. AREMA





Rail Type: 115 RE Section Number: 11525 Nominal Weight: 115 lbs/yd

Standard Length: 39', 80'

Standard Drilling: 3-1/2" X 6" or 3-1/2" X 6" X 6" with 1-1/8" dia. holes

Joint Bar Length: 24" or 36"

Joint Bar Weight: 4-Hole bars: 68 lbs/pr with hardware: 76 lbs/pr

6-Hole bars: 102 lbs/pr with hardware: 110 lbs/pr

Track Bolt: 1" X 6"

Area in²: 11.25

Section Modulus in³:

Head: 18.0 Base: 22.0 Moment of Inertia in⁴: 65.6

Tie Manufacture Specification – Cross and Switch

Material and Manufacture

- 1. Harwood ties shall be made from beech, maple, ash, oak and birch.
- 2. All ties must have a boxed heart. Ties manufactured by halving or quartering large logs are not acceptable.
- 3. All ties shall be made from sound, live, straight timber and shall be free from the following:

- Decay and Rot

- Large Knots

- Unsound Knots

- Splits over 3"

- Shakes

- Slanting Grain

Large or Numerous Holes

4. All Ties shall have bark completely removed.

Dimensions

1. Track ties shall be eight (8) feet long with the following face dimensions at the narrowest point:

No. 1 Ties Shall be squared with dimension of seven (7) inches thick with nine

(9) inches width of face.

No. 2 Ties Shall be squared with dimensions of six (6) inches thick with eight

(8) inches width of face.

Variations of one-half (1/2) inch over in thickness will be permitted. Ties may have wane one-half (1/2) inch wide on one or both corners of one side only.

2. Length Tolerance

- a) Cross ties plus one (1) inch
- b) Switch ties plus two (2) inches, minus one (1) inch

Machining of Cross Ties

Adzing – Hardwood Ties

1. No adzing required on any tie.

Boring - Harwood Ties

1. No boring is required for any tie.

Creosote Treatment

- 1. Seven (7) pounds per cubic foot of 50% creosote and 50% petroleum, or;
- 2. Kopper Creosote Petroleum Solution (Pressure Applications)
- 3. The ONTC will not be accepting ACZA ties (Crossties / Switch Ties) until we determine if the product is acceptable for our use.

Trimming

1. Trimmed ties shall be cleanly sawed at <u>both</u> ends to the specified length as they pass through the boring and adzing machine.

Branding


1. Branding of the ends of ties as the pass through the machine shall be with letters, figures, or symbols to indicate the following:


Year: 2024 Railway: O.N.R.


2. Letter height shall be approximately 1 ½ inches. Dies used for branding shall have a cutting edge of 1/8 inches wide shall indent the wood at least ¼ inch deep


Ontario Northland Railway
Office of the Director Rail Infrastructure

September 25, 2023










ITEM	LENGTH	STOCK	WEIGHT	
	LENGIN	NEW	PARTLY WORN	WEIGHT
TRACK SPIKE	5-1/2	01-03-012	01-03-013	0.750 LB.
TRACK SPIKE	6	01-41-014	01-41-015	0.813 LB.
SHIMMING SPIKE	6-1/2	01-03-018	01-03-019	0.875 LB.
SHIMMING SPIKE	7-1/2	01-03-021	01-03-022	1.000 LB.
SHIMMING SPIKE	8-1/2	01-03-024	01-03-025	1.125 LB.




THE MANUFACTURER'S IDENTIFICATION LETTER MUST APPEAR CLEARLY ON ALL SPIKES IN POSITION SHOWN.

LETTERS TO BE 1/4 " HIGH AND RAISED 1/32 ".

- C DOMINION STEEL & COAL CORP. LTD. E - PREMIER STEEL PRODUCTS LTD.
- H STEEL COMPANY OF CANADA LTD. V - PACIFIC BOLT MAN-WESTERN CAN. STEEL.
- NORTRAK LTD.

IDENTIFICATION MARKINGS FOR TRACK SPIKES



IDENTIFICATION MARKINGS FOR SHIMMING SPIKES

NOTES

- ALL SPIKES TO BE MANUFACTURED IN ACCORDANCE WITH SPECIFICATION 12-6 LATEST DATE.

THIS DRAWING SUPERSEDES DRAWING NO. S10C-8.1 DATED NOV. 15, 1962 & S10C-8.2 DATED FEB. 1, 1962

\$ 21	OC-8.2 DAT	ED FEB. 1, 1962			
4	JUNE'91	"DISPONIBLE EN	FRANCAIS" ADD	DED.	
3	APR.'90	V CHANGED TO	PACIFIC BOLT	MAN-WESTERN CAN. STE	EL.
2	JAN.'89	NOTES REVISED), MARKING UPD	ATED.	
1	JAN.'74	TOLERANCES /	LTERED.		
No.	Date	Révision			
	andard rme /	/	TRACK & S SPIKI FOR STANDAR	ES	
Drawi Dessi	MD (· ·	ecked G.W.M.	Approved Approbation	LL Gray Chief Engineer	
		hief Engineer l'Ingenieur en	Chef		
Date	SEPT.'73	3	Plan Number Dessin numera	TS - 1325	5

DISPONIBLE EN FRANCAIS

FILE: 1325.ts